

**STATE OF NEW HAMPSHIRE
DEPARTMENT OF EMPLOYMENT SECURITY**

**REQUEST FOR BID
RFB# NHES 2023-04
BIANNUAL INERGEN FIRE SUPPRESSION SYSTEMS INSPECTION**

ADDENDUM #1

RESPONSES TO RFB # NHES 2023-04, PROPOSAL INQUIRIES.

This Addendum #1 to RFB# NHES 2023-04 includes timely responses to proposer inquiries received by the required date of May 19, 2023, as follows:

Question # 1. My only question is about the size of the systems at each location. Do you have old inspection reports you can share?

NHES Response: Please see the attached Inspection Reports for the 45 South Fruit Street, Concord, NH and 6 West Townsend, Nashua, NH locations.

End of Proposal Inquiries.

Please include a signed copy of this signature page with your bid.

Vendor _____ Address _____

By: _____
(This document must be signed) (Title)

(Please print or type name) Tel.No. _____

**CONTACT: Erik Bal, Counsel
New Hampshire Employment Security
(603) 228-4084**



67 4th Ave., Needham, MA, 02492
T: 800.966.0000 | www.encorefireprotection.com

Date: 11/04/2021
Location: New Hampshire Employment Security
Location Street: 6 West Townsend
City/State/Zip: Nashua NH 03060
Primary Contact: Rocco Carter

ENGINEERED SUPPRESSION INSPECTION REPORT

System Location: Server Room Brand: ANSUL Agent: INERGEN

Type of Equipment in System

Control Panel: Z-10 AutoPulse
Ionization Smoke Detectors: 0 Photoelectric Smoke Detectors: 4 Heat Detectors: 0
Strobes: 1 Horn Strobes: 1 Bells: 0
Manual Pull Stations: 1 Abort Switches: 1 Reserve Switches: 0
Battery Quantity: 2 Battery Sizes: 12V7AH Battery Dates: 8-18
of Links: 0 Link Type/Size:
of Pressure Switches: 0 Connected to: EPO Building Fire Alarm Other: HVAC Shutdown

Inspection Tests Completed

Visual Inspection Control Panel Smoke Detectors
Strobes Horn/ Strobes Bells
Pull Stations Abort Switches Reserve Switches
Time Delays Building Alarm Connection Shutdowns
Discharge Heads Fire

Pass Fail

DEFICIENCIES & COMMENTS

No deficiencies have been discovered. See any additional comments below.
 DEFICIENCIES HAVE BEEN FOUND. For complete system status please also review the service trade work acknowledgement.
Comments:

Cyl. #	Tare Weight	Gross Weight	Net Weight	Hydro Date	PSI	Comments:
094010		350 Cu Ft		7-10	2175	Hoses 2020
094145		350 Cu Ft		7-10	2175	
094129		350 Cu Ft		7-10	2175	
095006		350 Cu Ft		7-10	2175	
094007		350 Cu Ft		7-10	2175	

ACCEPTANCE OF CUSTOMER OR CUSTOMER'S REPRESENTATIVE:
Customer ACKNOWLEDGES AND AGREES TO THE TERMS AND CONDITIONS ON NEXT PAGE; Customer also acknowledges that the services have been completed to Customer's satisfaction and the system/equipment has been left in service with the conditions noted in both this report AND the Service Trade work acknowledgement.

Customer:

Authorized Signature: _____

Print Name Here: _____

Encore Fire Protection:

Technician Signature: Chris Leach

Print Name Here: Chris Leach

FIRE ALARMS

FIRE SPRINKLERS

FIRE SUPPRESSION

FIRE EXTINGUISHERS



67 4th Ave., Needham, MA, 02492
T: 800.966.0000 | www.encorefireprotection.com

Date: 11/04/2021
Location: New Hampshire Employment Security
Location Street: 45 South Fruit St
City/State/Zip: Concord NH 03301
Primary Contact: Rocco Carter

ENGINEERED SUPPRESSION INSPECTION REPORT

System Location: Server Room Brand: ANSUL Agent: INERGEN

Type of Equipment in System

Control Panel: 442R
 Ionization Smoke Detectors: 0 Photoelectric Smoke Detectors: 4 Heat Detectors: 0
 Strobes: 1 Horn Strobes: 1 Bells: 1
 Manual Pull Stations: 1 Abort Switches: 1 Reserve Switches: 0
 Battery Quantity: 2 Battery Sizes: 12V7AH Battery Dates: 8-18
 # of Links: 0 Link Type/Size:
 # of Pressure Switches: 1-EPO Connected to: EPO Building Fire Alarm Other: Damper shutdown

Inspection Tests Completed

Visual Inspection	<input checked="" type="checkbox"/>	Control Panel	<input checked="" type="checkbox"/>	Smoke Detectors	<input checked="" type="checkbox"/>
Strobes	<input checked="" type="checkbox"/>	Horn/ Strobes	<input checked="" type="checkbox"/>	Bells	<input checked="" type="checkbox"/>
Pull Stations	<input checked="" type="checkbox"/>	Abort Switches	<input checked="" type="checkbox"/>	Reserve Switches	<input type="checkbox"/>
Time Delays	<input checked="" type="checkbox"/>	Building Alarm Connection	<input type="checkbox"/>	Shutdowns	<input type="checkbox"/>
Discharge Heads Fire	<input checked="" type="checkbox"/>				

Pass Fail

DEFICIENCIES & COMMENTS

No deficiencies have been discovered. See any additional comments below.

DEFICIENCIES HAVE BEEN FOUND. For complete system status please also review the service trade work acknowledgement.
Comments:

Cyl. #	Tare Weight	Gross Weight	Net Weight	Hydro Date	PSI	Comments:
9 Inergen cylinders		435 Cu Ft		1-07	2175	All ok Hoses 2020

ACCEPTANCE OF CUSTOMER OR CUSTOMER'S REPRESENTATIVE:

Customer ACKNOWLEDGES AND AGREES TO THE TERMS AND CONDITIONS ON NEXT PAGE; Customer also acknowledges that the services have been completed to Customer's satisfaction and the system/equipment has been left in service with the conditions noted in both this report AND the Service Trade work acknowledgement.

Customer:

Authorized Signature: _____

Print Name Here: _____

Encore Fire Protection:

Technician Signature: Chris Leach

Print Name Here: Chris Leach

FIRE ALARMS

FIRE SPRINKLERS

FIRE SUPPRESSION

FIRE EXTINGUISHERS